BRUHAT BANGALORE MAHANAGARA PALIKE

Modified of Community Property Maintenance (Including Parks) in JP Park in Ward No.17

Rate Analysis for EIRL Items

Item No.	Item of Work / Page. No.	Unit	Basic Rate	Area Weightage @ 6%	Total	Add TP @ -4.08%	Total Rate	Rate in Words
1	2	3	4	5	6	7	8	9
E-1	Removing & Refixing stone slabs of drains and pointing in C.M (1:3) (P. 27, It.No.5.33	Sqm	105.00	6.30	111.30	-4.54	106.76	Rupees One Hundred Six And Paise Seventy Six Only
E-2	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P. 143, It.No.19.1)	Cum	130.00	7.80	137.80	-5.62	132.18	Rupees One Hundred Thirty Two And Paise Eighteen Only
E-3	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm (P. 27, It.No.5.26.1)	Sqm	962.00	57.72	1019.72	-41.60	978.12	Rupees Nine Hundred Seventy Eight And Paise Twelve Only
E-4	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. - do - 10 cms thick (P. 27, It.No.5.31.2)	Sqm	912.00	54.72	966.72	-39.44	927.28	Rupees Nine Hundred Twenty Seven And Paise Twenty Eight
E-5	KSRB 5-9 : Providing chamfering edges to stone slab 2.5 cms. Wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 (P. 26, It.No.5.22)	Rmt	58.00	3.48	61.48	-2.51	58.97	Rupees Fifty Eight And Paise Ninety Seven Only
E-6	KSRB 5-8.1 : Providing one line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5.1.13 (P. 26, It.No.5.17)	Sqm	897.00	53.82	950.82	-38.79	912.03	Rupees Nine Hundred Twelve And Paise Three Only

Scanned with CamScanner

Item No.	Item of Work / Page. No.	Unit	Basic Rate	Area Weightage @ 6%	Total	Add TP @ -4.08%	Total Rate	Rate in Words
1	2	3	4	5	6	7	8	9
E-7	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregates /Sand/ Kanker / Moorum. KSRRB M100-1 : Placing tipper at loading point, loading with front end loader,dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH - 100/ Chapter 1 (P. 136, It.No.17.1)	Cum	95.40	5.72	101.12	-4.13	97.00	Rupees Ninety Seven Only

Assistant Engineer
Ward No.17

Assistant Executive Engineer
Yeshwanthapura Sub Division

Rates are hereby Approved

Executive Engineer
RR Nagara Division, RR Nagara

Chief Engineer
RR Nagara Zone, BBMP

Scanned with CamScanner